



Q.S OF BRACING OVER 2.4m SPAN - TRACKLOK®

Description	Qty	Rate	Total
TRACKLOK®	2	\$30.00 per brace	\$60.00
Labour	1hr	\$60.00 per hour	\$60.00
Steel Stud	2x2.4m	\$4.80 per length	\$9.60
Fixings	1 Sum	\$10.00	\$10.00
			\$139.60
			\$69.80 per brace

Q.S OF BRACING OVER 2.4m SPAN - Cut & Bent Stud

Description	Qty	Rate	Total
Steel Stud	2 x2.4m	\$4.80 per length	\$9.60
Timber 90.45 H1.2	2.4m	\$6.50 per length	\$15.60
Labour	1.5hrs	\$60.00 per hour	\$90.00
Fixings	1 Sum	\$10.00	\$10.00
			\$125.20
			\$62.60 per brace

Notes: Does not allow for seismic seperation.
 Voids ceiling installers PS3.
 Voids ceiling manufacturers warranty.
 Fails to meet AS/NZS1170.5

Q.S OF BRACING OVER 2.4m SPAN -Timber, Sleeve & Bent Stud

Description	Qty	Rate	Total
Timber Ex100x50mm	1x2.4m	\$3.80 per lm	\$9.12
Steel Stud	2x2.4m	\$4.80 per length	\$9.60
Bolts	6	\$2.00 per bolt	412.00
Sleeve to Fit Bolt	2	\$5.00	\$10.00
Labour	2hr 52mins	\$60.00 per hour	\$151.20
			\$191.92
			\$ 95.96 per brace

Notes: Does not allow for seismic seperaGon.
 Voids ceiling installers PS3.
 Voids ceiling manufacturers warranty.
 Fails to meet AS/NZS1170.5

* Figures sourced from practising Quantity Surveyors and excludes builders margins in all cases.